

Attachment #2  
Asphalt Sealing and Overlay RFP 2022  
#2022-01-045

## AREA 2

### **New Asphalt Drive Bit Base (Blue Area)**

\* Coverage: approximately 1428 square yards.

### **New Asphalt Under Lean To Bit Base Mix (Green Area)**

\* Coverage: approximately 1031 square yards

1. Grade/shape existing rock base as needed to establish proper drainage, and get area ready for 2" asphalt course. Rock will be rolled to compaction.
2. **Asphalt Base:** Install 2 inches asphalt base mix asphalt (Bit Base) and compact with vibratory roller. Taper edges of new asphalt as needed to blend into surrounding rock areas.

## FM ROCK AREA



### **New Asphalt Recycling Shed Area (Red Area)**

\*Coverage: approximately 532 square yards

1. Roto-mill butt joints as needed/ directed around perimeter of area to be overlaid to create a smooth transition to surrounding asphalt. All milling debris will be hauled off site.
2. Install riser rings in area to be paved, if needed.
3. Wedge in existing rock area with 2 inches BP-1 surface mix asphalt. Roll to compaction.
4. Clean up existing asphalt, as needed, and apply SS-1 Emulsion for bonding agent.
5. Overlay the entire red area with approximately 2 inches of BP-1 surface mix asphalt. Roll asphalt to proper compaction with steel drum vibratory roller.
6. All areas to be barricaded before, during and after this project.

### **RECYCLING SHED AREA**



### **NOTES**

1. Provide deduct amount if green area is not done.
2. All areas in Attachment #2 are flexible and can be scheduled easier than Attachment #1.